

Table LBW2.1a : Existing Water System summary - Pipes

PIPES	Length (m)			
Diam. (mm)	Bulk	Network	Total	%
Ashton				
≤ 45	0	0	0	0%
> 45 ≤ 75	0	32 330	32 330	53%
> 75 ≤ 125	0	7 060	7 060	12%
> 125 ≤ 175	0	5 215	5 215	9%
> 175 ≤ 275	100	12 151	12 251	20%
> 275 ≤ 375	1 870	2 275	4 145	7%
>375	0	0	0	0%
Ashton Total	1 970	59 031	61 001	100%
Bonnievale				
≤ 45	0	745	745	1%
> 45 ≤ 75	0	24 585	24 585	49%
> 75 ≤ 125	85	13 345	13 430	27%
> 125 ≤ 175	340	2 365	2 705	5%
> 175 ≤ 275	400	7 775	8 175	16%
> 275 ≤ 375	320	0	320	1%
>375	0	0	0	0%
Bonnievale Total	1 145	48 815	49 960	100%
McGregor				
≤ 45	0	1 170	1 170	9%
> 45 ≤ 75	0	8 195	8 195	62%
> 75 ≤ 125	165	3 160	3 325	25%
> 125 ≤ 175	465	5	470	4%
> 175 ≤ 275	0	0	0	0%
> 275 ≤ 375	0	0	0	0%
>375	0	0	0	0%
McGregor Total	630	12 530	13 160	100%
Montagu				
≤ 45	0	0	0	0%
> 45 ≤ 75	1 225	35 675	36 900	47%
> 75 ≤ 125	870	13 105	13 975	18%
> 125 ≤ 175	7 615	6 920	14 535	19%
> 175 ≤ 275	7 770	5 120	12 890	16%
> 275 ≤ 375	12 950	0	12 950	17%
>375	0	0	0	0%
Montagu Total	17 480	60 820	78 300	100%
Robertson				
≤ 45	0	0	0	0%
> 45 ≤ 75	0	36 380	36 380	39%
> 75 ≤ 125	0	35 220	35 220	38%
> 125 ≤ 175	0	13 180	13 180	14%
> 175 ≤ 275	0	7 540	7 540	8%
> 275 ≤ 375	0	250	250	0%
> 375	0	0	0	0%
Robertson Total	0	92 570	92 570	100%
Langeberg Total	21 225	273 766	294 991	100%